



## **SEA LOCK**



### CONSTRUCTION BARGES

# **SLK 01**

#### General

Type Construction Barge Module
Operator Australian Barge Hire Pty Ltd
Registration Australian Maritime Safety Authority

Built Australia
Construction Steel

Road Transport 2 standard Semi Trailers (2 barges per

trailer)

#### **Main Dimensions**

Length Overall	12.00	metres
Beam	2.50	metres
Depth	1.20	metres
Draft	0.20	Metres

Displacement 6.50 tonnes (unladen)

Load Capacity 20 tonnes



#### Operation

"Sea Lock Construction Barges" are interlocking barges developed to provide road transportable floating over water access solutions for our clients. The barges can be configured quickly and simply using the interlocking pin system developed by Australian Barge Hire.

#### **Features**

- Clear Deck
- Fast and Efficient establishment
- Interlocking connector system
- Ancillary equipment available

